



REINFORCEMENT DETAIL

TYPICAL FOR ALL WALLS, BAFFLES AND FOOTINGS



SMALL SEDIMENT FOREBAY LAYOUT

FOR INLET CULVERTS ≤ø525 OR CONTRIBUTING CATCHMENT AREA ≤1.5Ha



LARGE SEDIMENT FOREBAY LAYOUT

FOR INLET CULVERTS ≥Ø600 OR CONTRIBUTING CATCHMENT AREA >1.5Ha

NOTES

- 1. Refer to relevant section of the "Water Sensitive Urban Design" Guidelines" (Water by Design) and project drawings for sizing of forebay. Refer to project drawings for earthworks and setout details. Maintenance period 1 per year, Sediment Loading Rate 1.6T/Ha/Yr.
- 2. Refer to project drawings for stormwater inlet culvert and headwall type, sizing and invert level. Refer to Transport and Main Roads standard drawings, 1304 and 1305 for headwall details. For RCBC headwall and wingwall details refer to Transport and Main Roads standard drawing 1303.
- 3. Stormwater culvert may be rotated up to 10° (Max) from long axis of the forebay to suit site conditions.
- Baffle energy dissipators must only be installed on small sediment forebay as specified on Ipswich City Council standard drawing SD.16.
- 5. Refer to project drawings and IPWEAQ standard drawings. WSUD-001 to 004 for type, details and sizing of basin filter
- Construction tolerances as documented in the "Water Sensitive Urban Design Construction and Establishment Guidelines -Swales, Bioretention Systems and Wetlands" (Water by Design) must be achieved. Construction tolerances shall be noted on project plans. Invert levels and base levels shall be noted on project drawings.
- 7. Contraction joints to be provided to at 5m (Max) in concrete slab and 2m (Max) on access ramp.
- Access Ramp to extend to Council road network. Provide Commercial Driveway Invert and Slab, refer Ipswich City Council standard drawing SR.13 for details. Locking Rail to be installed to new driveway, refer Ipswich City Council drawing SR.36 for details. Access Ramp location may be varied to suit site conditions, refer to project drawings for alignment, setout and earthworks details.
- 9. Type 2 Tubular Steel Fence in accordance with Ipswich City Council standard drawing for SR.33 to be installed around all headwall/wingwall structures. To be extended adjacent access ramp large sediment forebay for length of side wall. Council's Engineer may direct that fencing be removed, however never where vertical drop off heights >= 1000mm. Fence posts may be bolted to the top of the concrete walls as an alternative to cast insitu footings.
- 10. For trash rack locations refer table below.
- 11. Insitu soil to remain under sediment forebay. Geotechnical engineer to confirm compaction requirements. Structural engineer to confirm footing requirements.
- 12. All dimensions are in millimetres unless noted otherwise.

Allowab	le Trash	Rack	Location		
Basin Size	Wall A	Wall B	- Wall C		
Small	No	Yes	No		
Large	Yes	Yes	Yes		

1	REVISIONS										
	AMENOMENT	INITIALS	DATE		AMENDMENT	INITIALS	DATE				
E				L							
E				K							
D		T		J							
C				1							
В				Н							
Q	A ORIGINAL ISSUE										



IPSWICH CITY COUNCIL

45 Roderick St P.O. Box 191 Ipswich QLD 4305

Tel (07) 3810 7894 Tel (07) 3810 7927 Fax (07) 3810 7950

APPROVED CHIEF OPERATING OFFICER (WPR) DATE 29 1/13

STANDARD DRAWING

SEDIMENT FOREBAYS TYPICAL LAYOUTS AND GENERAL NOTES **DRAINAGE**

SD.15

REV: A DRAWER: 100