



CONCRETE STEPS SECTION

NOTES:

1. Compacted Subgrade: Compact the existing subgrade material to 95% AASHO modified. Where the existing subgrade is not suitable for compaction, excavate and replace with suitable fill material, which will achieve the specified rate of compaction.
2. Finish all edges with steel edging trowel.
3. Handrails are to be applied to all steps in accordance with AS 1428.1-2009. ICC to approve handrail style and material.
4. Metal work fabrication to be hot dipped galvanised in accordance with AS 4680.
5. All welds to be in accordance with AS 1554 with continuous fillet welds and ground smooth.
6. Hazard Tactile Indicators to be installed in accordance with AS 1428.1-4 unless ICC advises otherwise.
7. Tread nosing to be applied to all steps in accordance with AS 1428.1-2009. ICC to approve and/or advise otherwise.
8. Step pavement colour and finish to best match adjacent pavement or otherwise ICC approved finishes.

REVISIONS					
AMENDMENT	INITIALS	DATE	AMENDMENT	INITIALS	DATE
F				L	
E				K	
D				J	
C				I	
B				H	
A	ORIGINAL ISSUE			G	

IPSWICH CITY COUNCIL
 45 Roderick St
 P.O. Box 191
 Ipswich QLD 4305
 Australia

Tel (07) 3810 7894
 Tel (07) 3810 7927
 Fax (07) 3810 7950

APPROVED

 CHIEF OPERATING OFFICER (WPR)
 DATE 29-7-13

STANDARD DRAWING

STEPS - CONCRETE

PARKS

SP.105

REV: A DRAWER: 100